BRUHAT BANGALORE MAHANAGARA PALIKE

BBMP/2018-19/OW/WORK_INDENT34772

APPROVED SCHEDULE - B

.E/BTP/BBMP/E-PMT/22/2018-19, Date: 27.02.2019

Repair works of public toilets at Agrahara layout and Vinayakanagara in ward no 5

Sl. No.	Approved Qty.	Description	Unit	Approved Tender Rates of NARAYANARAO S ( )	
				In Figures	In Words
1	21.6	KSRB 2-2.2 : Earthwork excavation for foundation of buildings, water supply, sanitary lines and electrical conduits either in pits or in trenches 1.5m and above in width, in hard soil not exceeding 1.5 m. in depth including dressing the bottom and sides of pits and trenches, stacking the excavated soil clear from edges of excavation with lead upto 50 m. after breaking of clods complete as per specifications. specification. No. KBS 2.1(b) / 2.3.5.	cum	288.83	Rupees Two Hundred Eighty Eight and Eighty Three Paise Only
2	48	Providing and installing at site of work 63mm (0.662) PVC Pipes of 6 kg / cm2 including cost of pipes and specials and labour, including lowering into trenches, laying true to line, level and perfect linking at joints leak proof including jointing of approved type with all labour and lift charges, handling charges including encasing the pipe alround to a depth not less than 15cms with gravel or selected earth available from the excavation etc., complete (P.NO - 94, I.NO - 13.73.2, PWD SR 16-17)	No	348.59	Rupees Three Hundred Forty Eight and Fifty Nine Paise Only
3	21.6	Refilling available earth around pipe lines, cables in layers not exceeding 20cms in depth, compacting each deposited layer by ramming after watering with lead upto 50m and lift upto 1.5m including cost of all labour complete as per specifications (P.NO - 6, I.NO - 2.11, PWD SR 16-17)	Sqm	76.13	Rupees Seventy Six and Thirteen Paise Only
4	15.75	PVC DOOR Shutter : Supply and fixing of doors shuttersmade of rigid PVC extruded hollow section of 20mm X 200mm with the wall thickness of 1.0mm + /0.1mm equally divided into 4nos with tongue and groove locking arrangements. The shutter frame is made of 58*24 mm with the wall thickness of 1.5mm+/-0.15mm section metricut and joined at 4 corners with 125mmX225mm plastic brackets. The shitter shall be horizontally reinforced with 2nos of 8mm PVC rods. Teak wood battons shall be reinforced inside the door shutter during the fabrication of the door shutter at those points wherever the hardware is fixed on to the door shutter.	sqm	1796.26	Rupees One Thousand Seven Hundred Ninety Six and Twenty Six Paise Only
5	93.92	KSRB 15.14.3 : Providing and applying one coat with oil bound washable distemper of approved brand and shade on wall surface including priming coat with distemper primer after througly brooming the surface free from mortar drops and other foreign matter including preparing the surface even and sand paper smooth, cost of materials, labour, complete as per specifications. PWD-2018-19	Sqm	46.95	Rupees Forty Six and Ninety Five Paise Only
6	75.42	Providing and finishing external walls in two coats over one coat of 100% acrylic silicon glazed primer with antifungal paint for top coat of approved brand and shade to give an even shade after thoroughly brooming the surface to remove all dirt and loose powdered material, free from mortar drops and other foreign matter cost of materials, labour, complete as per specifications.	Sqm	154.11	Rupees One Hundred Fifty Four and Eleven Paise Only
7	14.64	KSRB 14.14-5 : Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. ceramic tiles 400X400X20mm	sqm	1202.27	Rupees One Thousand Two Hundred Two and Twenty Seven Paise Only
8	60.66	KSRB 14.14-5 : Providing ceramic tiles of approved make, shade and size for flooring, treads of steps and landings laid on a bed of 12mm thick, cement mortar 1:3 mix, flush pointing with white cement using colour pigment, including cost of materials, labour, curing, complete as per specifications. ceramic tiles 15X15cms 6mm thick	sqm	944.06	Rupees Nine Hundred Forty Four and Six Paise Only

Signature of the contractor

10/05

Executive Engineer

oved ty.		Description	Unit	Approved Tender Rates of NARAYANARAO S ( )	
				In Figures	In Words
	60	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fittings including fixing the pipe with clamp at 1.00 mtr spacing. This includes jointing of pipes and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall) - 20mm dia CPVC pipe .	mtrs	127.58	Rupees One Hundred Twenty Seven and Fifty Eight Paise Only
10	40	25mm dia CPVC pipe .	mtrs	168.4	Rupees One Hundred Sixty Eight and Forty Paise Only
11	40	32mm dia CPVC pipe .	mtrs	219.43	Rupees Two Hundred Nineteen and Forty Three Paise Only
12	4	Providing and fixing CI Nahani trap of approved make conforming to ISI specifications and construction of Cistern in M-15 as per directions (Rate is inclusive of cost of materials and fixtures and conveyance of materials to work spot).	each	290.87	Rupees Two Hundred Ninety and Eighty Seven Paise Only
13	10	KSRB13-6.1-1 : Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification No.KBS 13.2.2 / 13.3	each	235.76	Rupees Two Hundred Thirty Five and Seventy Six Paise Only
14	2	KSRB 13-11.1 : Providing and placing on terrace, polyethylene water storage tanks as per IS 12701 : 1996 with manhole lid and suitable locking arrangements, making holes of suitable diameter for inlet, outlet and over flow pipes, including cost of all materials, labour, transport charges, HOM of equipments and testing complete as per specifications. (For 1000 litre capacity)	no	8641.42	Rupees Eight Thousand Six Hundred Forty One and Forty Two Paise Only
15	4	KSRB 11-5 : Providing and fixing white vitreous china clay, water closet European type (Pedestal type, P-trap) with black solid plastic seat and lid, C.P brass hinges, rubber buffers. 10 litre low level, P.V.C flushing cistern (all are approved make) with fittings, C.I/M.S brackets, 40mm diameter flush bend with fittings and clamps, overflow arrangements with special and 25mm mosquito proof coupling of approved design, painting of fittings and brackets, including cost of materials, labour complete as per specification.	each	5235.68	Rupees Five Thousand Two Hundred Thirty Five and Sixty Eight Paise Only

Signature of the Contractor

Executive Engineer
Byarayanapura Division
BBMP, Bangalore - 92

10/05

10/05